

Structures

Master Specification

ST-BF-C4 Bridgework Sundries

Document Information

KNet Number:	13434834
Document Version:	4
Document Date:	August 2021

DEPARTMENT FOR
INFRASTRUCTURE
AND TRANSPORT



Government of South Australia
Department for Infrastructure
and Transport

Document Amendment Record

Version	Change Description	Date
1	Initial issue (formerly S55)	28/06/19
2	Formatting for publishing	19/09/19
3	Amendment to Clause 1; Plaque requirements removed	August 2020
4	Clauses 1.1, 1.2, 1.13, 3.1 clarified	August 2021

Document Management

This document is the Property of the Department for Infrastructure and Transport and contains information that is confidential to the Department. It must not be copied or reproduced in any way without the written consent of the Department. This is a controlled document and it will be updated and reissued as approved changes are made.

Contents

Contents	3
ST-BF-C4 Bridgework Sundries	4
1 Traffic and Pedestrian Barriers	4
2 Miscellaneous Concrete Work	5
3 Bridge Light	5
4 Hold Points	5

ST-BF-C4 Bridgework Sundries

1 Traffic and Pedestrian Barriers

General

- 1.1 This Clause specifies the requirements for the fabrication and erection of steel barrier components (other than proprietary components supplied as part of a GD300-approved barrier system) and extruded aluminium alloy railings.

Design Standards

- 1.2 Unless specified otherwise, all design and / or documentation must comply with the most recent revisions (including published amendments) of the following design standards and / or specifications:
- AS 1554.1 Welding of Steel Structures.
 - AS 2205 Methods of Destructive Testing of Welds in Metal.

Materials

- 1.3 Materials and parts used in fabrication of components shall comply with the requirements of the Australian Standards as shown on the Drawings.

Fabrication

- 1.4 Fabrication of steel barrier components shall be undertaken in accordance with ST-SS-S1 "Fabrication of Structural Steelwork" and the requirements of this Part. All welds shall be prequalified in accordance with Clause 4.3 of AS 1554.1 and subject to visual inspection of work in accordance with Clause 6.2 of AS 1554.1.
- 1.5 At least 7 days' notice shall be given of commencement of fabrication of the traffic and / or pedestrian barrier.
- 1.6 Provision of the notice and weld prequalification supporting information shall constitute a **Hold Point**.
- 1.7 Dimensions shown on the Drawings are specified at 20°C. Posts and splice connections in rails shall be jig fabricated; all post base plates shall be drilled using the same template. Post to base plate welds shall comply with the SP Category of AS 1554.1. All other welds shall comply with the GP Category of AS 1554.1. Welds shall be subject to approval.
- 1.8 Electrodes shall comply with and be classified in accordance with AS 1553. Welds shall be finished as smooth as practicable. Where the finish on an exposed weld is not as smooth as practicable, the weld shall be ground to a smooth shape.
- 1.9 Corners on exposed edges of steel plates shall be rounded to a radius of approximately 2 mm. All burrs on aluminium components shall be removed. Fabrication shall be completed and all welds cleaned before galvanizing.

Protective Treatment

- 1.10 The contractor shall provide at least 7 days prior notice of the application of protective treatment.
- 1.11 Provision of the notice shall constitute a **Hold Point**.
- 1.12 Steel components shall be galvanized in accordance with ST-SS-S3 "Galvanizing".
- 1.13 The protective treatment of aluminium components shall comply with the following:
- components shall be anodised after fabrication;
 - the anodised film shall have a minimum thickness of 25 µm (AA 25) and shall provide the maximum hardness and scratch resistance;
 - handrails, handrail spigots and end caps shall be medium bronze colour; and

- d) crash rail components and handrail fixing clamps shall be a natural silver colour.
- 1.14 Six weeks before ordering aluminium extrusions, the Contractor shall supply at least two samples of each anodised aluminium extrusion. The colour of extrusions used in the works shall match the colour of the samples.
- 1.15 Provision of the samples shall constitute a **Hold Point**.

Transportation, Handling and Storage

- 1.16 Components shall be packed, supported, transported, handled and stored so that the components are kept clean and free from damage to the material or finish.
- 1.17 Posts, rails and panels shall be stored under cover and above ground and shall be protected against damage. At least 7 days' notice shall be given prior to transport of the components to site.
- 1.18 Provision of the notice shall constitute a **Hold Point**.

Erection

- 1.19 Anchor bolts and shear nuts shall be cast into the kerbs using rigid templates temporarily secured in position to kerb formwork. Posts and panels shall be erected as detailed on the Drawings; railing shall be erected true to grade of the structure.
- 1.20 Deviation from the correct alignment of the posts, rails and panels shall not exceed 3 mm. The Contractor shall allow for the final adjustments of gaps between rails after completion of erection.

2 Miscellaneous Concrete Work

- 2.1 Unless shown as non-structural concrete on the Drawings or specified by the Principal, miscellaneous concrete work (such as concrete drains, sumps and edge beams) shall be constructed as shown on the Drawings and in accordance with ST-SC-S7 "Supply of Concrete".

3 Bridge Light

- 3.1 Where a bridge light is required, then unless shown otherwise on the Drawings or specified by the Principal, the Contractor shall:
- supply lighting components in accordance with RD-EL-S1 "Supply of Lighting Components"; and
 - carry out electrical work for bridge lighting in accordance with the relevant clauses of RD-EL-C1 "Installation of Lighting for Roads and Public Spaces."

4 Hold Points

- 4.1 The following is a summary of Hold Points referenced in this Part:

Table ST-BF-C4 4-1 Hold Points

Document Ref.	Hold Point	Response Time
1.16	Notification of commencement of fabrication and weld prequalification information	2 Working Days
1.11	Notification of application of protective treatment	2 Working Days
1.15	Provision of anodised aluminium extrusion samples	7 Working Days
1.18	Notification of transportation of the components to site	2 Working Days